

Section 31 00 00 – Earthwork (Maintenance; Common Work Results; Schedules)

1. See also Division 01 for General Requirements.
2. See also Division 02 for Site Construction.
3. See also Division 03 for Concrete.
4. See also Division 32 for Exterior Improvements.
5. See also Division 33 for Utilities.
6. See also appendices for various space type requirements.
7. Tunnels and buried utilities must be located prior to jack-hammering, excavation, etc. If tunnel ceiling damage occurs this must be adequately repaired at the contractor's expense.
8. FS Cartographer locates shall be initiated through 'one-call' to City of Eugene.
9. When designing within tunnels clear walkways, service areas, and other accesses must be maintained.
10. No site drainage piping internal to buildings.

End of Section

Section 31 10 00 – Site Clearing (Selective Tree & Shrub Removal & Trimming; Earth Striping & Stockpiling)

1. See also Section 01 56 00 for Tree and Plant Protection & Preservation.
2. No existing onsite topsoil, or stockpiled soil, may be re-used without PM and FS Exterior Supervisor approval.
3. Tree Removal:
 - a. Removal of trees is subject to FS Exterior Supervisor review and approval as well as the requirements described in the Campus Tree Plan.
 - b. If trees are to be removed and they are located within construction fencing, then fencing is to be installed and posting of tree removal is to be placed on the fencing.
 - c. If trees are to be removed and they are located outside of construction fencing, then each tree is to be posted for removal for a minimum of 2 weeks prior to removal.
 - d. ALL trees to be removed over 6-inches caliper are to be individually posted for removal at least 2-weeks prior to removal.
 - e. Postings are to include PM contact information.

End of Section

END OF DIVISION 31